

Rye Park Wind Farm Yass Street road upgrades



Frequently Asked Questions

- **When will the Yass Street road upgrade works commence?**

Works are expected to commence in February 2022. They are likely to be completed in March-April 2022.

- **At which end of Yass Street will you start?**

Works will commence at the north-end of Yass Street, as a continuation of the works required from the Grassy Creek Road upgrade.

- **How long are the works expected to take?**

Approximately two months. Traffic control will be implemented to safely deliver the works.

- **What hours of the day will works take place?**

Works will be as per the Project's approved hours in the Development Consent:

Monday to Friday, 7:00 am to 6:00 pm, Saturday, 8:00 am to 1:00 pm

- **What will happen to my driveway? Will it get shortened / widened / improved drainage?**

Driveways will be reconstructed to tie into the new road level. The pre-existing finish (e.g. gravel, seal) of the driveway will be maintained as a minimum standard. Where applicable, pipes for drainage may be required to be installed.

- **Will I be able to access my property while works are going on?**

Yes, access will be made available for you and the construction team will keep open communications with residents throughout the process. The road pavements will be placed in a manner that will always have access and the sealing will take place over 1 day, only stopping access to any particular driveway for 30 mins to 1 hour at that time.

Process: Import and preparation removing pot holes, application of bitumen and rolling, application of line marking and road furniture.

- **If I am not home when you need to start works, how will I know if I can access my driveway upon my return?**

We will be in touch before the commencement of works that could impact your driveway.

- **Who is the best point of contact for these works?**

Tilt Renewables - Site HSEC Manager: **Andrew Galland - 0447 076 886**

Zenviron - Site Manager: **Mark Cha - 0460 290 262**

- **Will any trees be impacted during these works?**

The current road upgrade design (subject to Council approval) avoids the need to impact any trees along Yass Street.

- **How much higher will the upgraded road be vs. existing driveways?**

Approximately 150mm raised from the existing profile.

- **When will the sealing in front of the Hall take place?**

The full sealing scope in Yass Street will be completed over a 1-2 day period during the period of the works noted above.

- **How is the causeway being replaced – to address water/drainage?**

The causeway on Yass Street is a localised low point for Yass Street. The scope of the road upgrade is to widen the road to facilitate use by Project traffic. The design level of the new causeway will be approximately 150mm higher than the current causeway. This will help alleviate pooling of water on the road. The broader issue of where water from the road reserve drains to is beyond the scope of the upgrades and is being discussed with Council.



For any questions or feedback, please get in touch by calling: **1800 WE TILT** (938 458)

Email: ryeparkwindfarm@tiltrenewables.com | Web: www.ryeparkwf.com.au

Postal Address: PO Box 16080 Collins St West, Melbourne Vic 8007

Sign up for updates by subscribing to the newsletter and construction updates via SMS

Use the QR code provided to sign up or contact us on 1800 WE TILT and we'll do it for you.

You can text us too! Text +61 480 096 779 if you have any questions and we'll give you a call back.